

Baug

Additional information please contact:

Borr Drilling Management DMCC
 Level 28 Reef Tower, Cluster O
 P.O. Box 36913
 Jumeirah Lakes Towers, Dubai United Arab Emirates
 +971-04-4487501

marketing@borrdrilling.com - www.borrdrilling.com

High Specification Jackup

General Description

Design / Generation Friede and Goldman L-780 Mod VI
Constructing Shipyard Far East Levingston, Singapore
Year Entered Service / Significant Upgrades1991
Classification..... ABS, A-1
Flag Vanuatu
Overall Dimensions..... 244ft. long x 250ft. wide x 36ft. deep
Legs 3 x 560ft. long, Triangular Truss
Drafts 22ft. load line draft
Accommodation 120 persons
Displacement..... 49,731kips operating
Variable Deck..... 7,200st operating / 3,600st transit
Transit Speed up to 5knots
Operating Water Depth 394 ft. designed / 394 ft. outfitted
Maximum Drilling Depth 30,000ft.

Drilling Equipment

Derrick Brown Service, 170ft. high, with 40ft. x 40ft. base.
Hookload Capacity 1,500,000lbs. gross nominal capacity.
Cantilever 67ft. reach, forward / aft 15ft. port / 15ft. stbd. of rig centerline.
Drawworks National Oilwell E-3000, 3,000hp 1,662,000 with 16 x 1- 3/4" drilling linesstrung.
Rotary Table National Oilwell D-495 with a 49-1/2" opening;
Top Drive Varco TDS-4H 750hp and rated to 45,500ft.-lbs. continuous drilling torque in low gear.
Tubular Handling Varco PHM-3i pipe racking system, complete with a vertical 2 arm floor mounted remotely operated system.
Mud Pumps 3 x National Oilwell 14-P-200 triplex pumps, each driven by 2 GE 752 traction motors.
HP Mud System Rated for 6,000psi.
Solids Control 3 x Axiom AX-1 shaleshakers.

Power & Machinery

Main Power 4 x Caterpillar 3606 diesel engines rated at 1,830kW, 900rpm, each driving 1 x 3,000kVA AC generator
Emergency Power 1 x Caterpillar D398 TA diesel engine rated 1,600kW, 1,200rpm driving 1 x AC generator.

Storage Capacities

Fuel Oil..... 3,431 bbls.
Liquid Mud..... 4,987 bbls. Active
Base Oil 1,636 bbls.
Brine..... 1,636 bbls.
Drill Water 26,191 bbls.
Potable Water 4,070 bbls.
Bulk Material (mud + cement) 18,200 cu.ft.
Sack Storage 5,000 sacks.

BOP & Well Control Equipment

BOP Rams 1 x Hydril 21-1/4" 5,000psi; 3-ram preventer; (1 x Double and 1 x Single).
 1 x Hydril 13-5/8" 15,000psi 4-ram preventer; (2 x Doubles).
BOP Annulars 1 x Hydril GL 21-1/4" 5,000psi annular preventer.
 1 x Hydril GX 13-5/8" 10,000psi annular preventer.
BOP Handling VMW Industries / hydraulic BOP crane 1 x 100st main hoist.
Diverter DrilQuip 49-1/2" with a pressure rating of 750psi and 2 x 16" flow lines.

Mooring Equipment

Mooring Winches 4 x Intercontinental SD 200, 75,000lbs pull capacity.
Anchor Lines 4 x 2" IWRC galvanized wire rope.
Anchors 4 x Delta Flipper 8st anchors.

Cranes

Cranes# 1,2 & 3 3 x Manitex ML4800/HD with 130ft. booms rated to 28st.

Special Features & Other Information

Helideck Rated for S-61N or S-92 helicopters



These specifications are intended for general reference purposes only, as actual equipment and specifications may vary based upon subsequent changes, the contract situation and customer needs. All equipment shall be operated and maintained at all times, in compliance with Borr Drilling standard operating manuals, policies and procedures, and within its stated operational limits or continuous rated capacity, in order to assure maximum operational efficiency.

