

Fonn

Additional information please contact:

Borr Drilling Management DMCC
 Level 28 Reef Tower, Cluster O
 P.O. Box 36913
 Jumeirah Lakes Towers, Dubai United Arab Emirates
 +971-04-4487501

marketing@borrdrilling.com - www.borrdrilling.com

High Specification Jackup

General Description

Design / Generation Friede & Goldman L-780 Mod V
Constructing Shipyard Far East Levingston, Singapore
Year Entered Service / Significant Upgrades 1986 / N/A
Classification..... ABS A-1 Self Elevating Drilling Unit
Flag Vanuatu
Overall Dimensions..... 228ft. long x 222ft. wide x 31ft. deep
Legs 3 x 496ft. long, Triangular Truss
Drafts 19ft. Draft at loadline
Accommodation 114 persons
Displacement..... 19,668st
Variable Deck..... Maximum of 7300st operating / 4,626st transit
Transit Speed 4 knots (Previous rig move data)
Operating Water Depth 361ft. designed / 361ft. outfitted
Maximum Drilling Depth 30,000ft.

Drilling Equipment

Derrick JA Paris API Type 4A, 160ft. high, with 36ft. x 36ft. base.
Hookload Capacity 1,400,000lbs. gross nominal capacity.
Cantilever Rotary position can be up to 52ft. aft of transom, and up to 15ft. port or starboard of the Rig Centre line.
Drawworks Continental Emsco C-3 Type 2, 3x Jeumont Schneider CIR 423 electric motors; 3,000hp, 1,399,935 lbs. with 14 pull lines.
Rotary Table Continental Emsco T4950 49-1/2" hydraulic, 800st
Top Drive Varco TDS-4S, 716st capacity, with an electric motor, rated to 45,500ft.-lbs. continuous drilling torque in low.
Tubular Handling AR 3200-C Iron Roughneck.
Mud Pumps 3 x Continental Emsco FB1600 1,600hp Triplex pumps, each driven by 2 x Jeumont Schneider CIR423 traction motors.
HP Mud System Rated for 5,000psi
Solids Control 3 Brandt VSM 300

Power & Machinery

Main Power 4 x Wartsila x 12V22MD diesel engines rated at 1,520kW, 900rpm, each driving 1 x 2,050kVA AC generator.
Emergency Power 1 x Caterpillar 3412 diesel engine rated 438kW, 1,800rpm driving 1 x AC generator.

Storage Capacities

Fuel Oil..... 2,045 bbls.
Liquid Mud 2,337 bbls.
Base Oil..... 1,149 bbls.
Brine..... 4,025 bbls.
Drill Water 4959 bbls.
Potable Water 2,362 bbls.
Bulk Material (mud + cement) 12600 cu.ft.
Sack Storage5000 sacks

BOP & Well Control Equipment

BOP Rams 1 x QOP Double 'U' 21-1/4" 2,000psi ram preventer.
 2 x Shaffer SL Double 13-5/8", 10,000psi ram preventer (4 x rams total).
BOP Annulars 1 x Hydril Type MSP 21-1/4", 2,000psi annular preventer.
 1 x Hydril Type GX 13-5/8", 5,000psi annular preventer.
BOP Handling Beebe International Plc. Pneumatic 39.7st
Diverter 49-1/2" 500 Vetco KFDJ 500 FDS diverter with 16" flow line.

Mooring Equipment

Mooring Winches 4 x Brissonneu & Lotz Marine x 40/130T; 88,160 lbs. rated pull.
Anchor Lines 4 x 2" x 2000ft. British Wire Rope.
Anchors N/A

Cranes

Cranes 1 and 2 2 x Skagit 363, 39.7st with 120ft. Booms (Port and Stbd)
Crane 3 1 x Skagit 363, 39.7st with 120ft. boom (Aft)

Special Features & Other Information

Helideck Rated for Sikorsky S-61 and S-92 (max 10.5st) 83 diameter.
Cond. Tensioning Primary: rated at 350st, with 4 x lift points, Secondary: 176st, with 6 x lift points.
RPD System Yes



These specifications are intended for general reference purposes only, as actual equipment and specifications may vary based upon subsequent changes, the contract situation and customer needs. All equipment shall be operated and maintained at all times, in compliance with Borr Drilling standard operating manuals, policies and procedures, and within its stated operational limits or continuous rated capacity, in order to assure maximum operational efficiency.

