

**Additional information please contact:**

Borr Drilling Limited
 E. Pearman Building, 2nd Floor
 9 Par-la-Ville Road,
 Hamilton HM11, Bermuda

marketing@borrdrilling.com - www.borrdrilling.com

High Specification Jackup**General Description**

Design / Generation Friede & Goldman L-780 Mod VI Universe Class
Constructing ShipyardFar East Levingston, Singapore
Year Entered Service / Significant Upgrades 1999 / N/A
Classification..... ABS A-1 Self Elevating Drilling Unit
Flag.....Vanuatu
Overall Dimensions 244ft. long x 250ft. wide x 36ft. deep
Legs..... 3 x 560ft. long, Triangular Truss
Drafts.....23ft. at loadline
Accommodation 140 persons
Displacement..... 28,647st at load line
Variable Deck..... 12,000kips operating / 6,870kips transit
Transit Speed up to 5knots
Operating Water Depth..... 394ft designed
Maximum Drilling Depth.....30,000ft

Drilling Equipment

Derrick Drecto, 170ft. high, with 40ft. x 40ft. base.
Hookload Capacity 1,600,000lbs. static hook load.
Cantilever 60ft. reach, forward / aft 15ft. port / 15ft. stbd. of center .
Drawworks National Oilwell E-3000, 3 x GE 752 DC electric motors; 3,000hp, 1,246,000lbs. with 14 lines.
Rotary Table Varco BJ RST 49-1/2" hydraulic, 1,000st 40,000ft.-lbs. torque.
Top Drive Varco TDS-4SI, 750st capacity, with 1 x GE 752 high torque motor, rated to 45,500ft.-lbs. continuous drilling torque in low gear.
Tubular Handling Varco BJ PRS-3i and AR 3200-C Iron Roughneck.
Mud Pumps 3 x National Oilwell 14-P-220, 2,200hp 6,000psi Triplex pumps, each driven by 2 x GE 752 high torque traction motors.
HP Mud System Rated for 6,000psi.
Solids Control 5 x Thule VSM 300 shale shakers, 3 x Brandt LCM-2 mud conditioners.

Power & Machinery

Main Power 4 x Wartsila x 12V200 diesel engines rated at 2,100 kW, 1,200 rpm, each driving 1 x 3,000 kVA ACgenerator.
Emergency Power 1 x Caterpillar D3508 diesel engine rated 600 kW, 1,800 rpm driving 1 x AC generator.

Storage Capacities

Fuel Oil 3,491 bbls
Liquid Mud 5,000 bbls
Base Oil 1,627 bbls
Brine 1,627 bbls
Drill Water 32,874 bbls
Potable Water 4,069 bbls
Bulk Material (mud + cement) 18,200 cu.ft.
Sack Storage..... 5,000 sacks

BOP & Well Control Equipment

BOP Rams Varco Shaffer 18-3/4", 15,000psi; 2 x double ram NXT preventers.
BOP Annulars 1 x Varco Shaffer 18-3/4" 10,000psi annular preventer.
BOP Handling VMW Overhead Bridge crane, 125st
Diverter 49-1/2" 500psi Drill Quip FDS diverter with 16" flow Line.

Mooring Equipment

Mooring Winches 4 x Intercontinental SD 200, 75,000lbs pull capacity.
Anchor Lines 4 x 2" 6x36 IWRC 3,000ft. useable length.
Anchors 4 x Delta Flipper 7.5st anchors.

Cranes

Cranes 1 and 2 2 x 39.7st (@ 60ft) Seatrax 6032, 120ft. booms (Port and Stbd.)
Crane 3 1 x 39.7 st (@ 60ft) Seatrax 6032 130ft. boom (Aft)

Special Features & Other Information

Helideck Rated for Sikorsky S-61N, S-92 helicopters; 85ft x 85ft
Conductor Tens Rated at 300st, with 4 x lift points.
RPD System N/A
Other Pipe deck machine and conveyor.



These specifications are intended for general reference purposes only, as actual equipment and specifications may vary based upon subsequent changes, the contract situation and customer needs. All equipment shall be operated and maintained at all times, in compliance with Borr Drilling standard operating manuals, policies and procedures, and within its stated operational limits or continuous rated capacity, in order to assure maximum operational efficiency.

