

Gunnlod

Additional information please contact:

Borr Drilling Limited
E. Pearman Building, 2nd Floor
9 Par-la-Ville Road,
Hamilton HM11, Bermuda

marketing@borrdrilling.com - www.borrdrilling.com

High Specification Jackup

General Description

Design / Generation	PPL Pacific Class 400
Constructing Shipyard	PPL Shipyard PTE Ltd. , Singapore
Year Entered Service / Significant Upgrades	2018
Classification	ABS,A1, Self-Elevating Drilling Unit
Flag	Panama
Overall Dimensions	236.5 ft.long x 224.4 ft.wide x 27.9 ft deep
Legs	(3) 532 ft. long, Triangular
Drafts	19.50 ft at loadline
Accommodation	150 persons
Displacement	43,845 kips
Variable Deck	7,498 kips operating / 4,998 kips transit (spud cans full)
Transit Speed	up to 4 knots, @ 150st bollard pull
Operating Water Depth	400 ft. designed/ 400 ft. outfitted
Maximum Drilling Depth	30,000ft

Drilling Equipment

Derrick	Loadmaster Derrick 160 ft. high, with 35 ft. x 35 ft. base
Hookload Capacity	1,500,000lbs gross nominal capacity
Cantilever/ Drill floor	75 ft / 15 ft Port & Stbd
Drawworks	Cameron Ultrahoist 750-3000(FA30) Max hook load 750st with 14 lines. 2 x GE AC motors suitable for 1-5/8" drill line
Rotary Table	Cameron 49-1/2" table opening, hydraulic drive, rated 750st
Top Drive	Cameron FD35, 750st static/dynamic load rating 1150hp AC motor GE. Max speed 274rpm, Max torque 66,000 ft.-lbs. Max MU/BO torque 115,000ft.-lbs, (2) IBOP 3 1/6" – 15k
Tubular Handling	Cameron JiM 10 T-P-L, 3-1/2" to 9-3/4" OD drill pipe & drill collar Make-up torque 103,300ft-lb Break-out torque 147,500ft-lb Spinning speed 0-80 rpm (with 5" OD) Spinning torque 3,500ft-lbs
Mud Pumps	(3) Lewco W2214 triplex pumps, each driven by 1150 hp (GE AC motor) 7,500 psi rated
Solids Control	(4) NOV Brandt VSM 300 shaleshakers. Mud cleaner installed over one shale shaker.

Power & Machinery

Main Power	(5) Caterpillar 3516C-HD diesel engines rated at 2,150hp at 1200rpm each with Kato generator rated to 2,150KVA
Emergency Power	(1) Caterpillar 3508B DITA diesel engine rated at 1,298hp at 1,800rpm with Leroy Somer generator rated to 1020KVA

Storage Capacities

Fuel Oil	4,170 bbls
Liquid Mud	4,170 bbls
Base Oil	1,270 bbls
Brine	1,289 bbls
Drill Water	21,742 bbls
Potable Water	3,553 bbls
Bulk Material	(mud + cement) 11,653 cu-ft
Sack Storage	5,000 sacks

BOP & Well Control Equipment

BOP Rams	(2) Cameron double rams 18-3/4" 15k psi BOP
BOP Annular	(1) Cameron 18-3/4" 10,000psi annular preventer
BOP Handling	(2) J D Neuhaus EH-75 BOP main hoists, rated 75mt each
Diverter	Vetco KFDJ 500, 49-1/2" diverter rated to 500psi with (1) 16" flow line, (2) 12" overboard, (1) 6" deluge and (1) 3" fill line

Mooring Equipment

Mooring Winches	(4) Mentrade electric winches rated at 31mt capacity 63.5mt brake holding
Anchor Lines	3000ft x 1-1/2" galvanized wire rope
Anchors	(4) Flipper Delta anchor

Cranes

Cranes	(3) Favello Favco cranes, 50mt capacity, 120ft boom
---------------	---

Special Features & Other Information

CTU	TSC 225mt Vertical Load and 25mt Lateral Load - hydraulic driven @ 4.66 m and 10.66 m from AFT transom
RPD System	Yes
Helideck	Rated for Sikorsky S-61 and S-92 helicopters. CAP 437
Offline Systems:	
Iron Roughneck	(1) Cameron JiM 10 T-P Iron Roughneck. 3-1/2" to 9-3/4" OD
MPC	FORUM MPC (Multi-Purpose Crane) of 6,000 lbs SWL at all radii, crane boom end is adapted for mounting of a 280-kg man-basket
OA Crane	OAC (Offline ActivityCrane) Forum 10mt derrick mounted for offline pipehandling



These specifications are intended for general reference purposes only, as actual equipment and specifications may vary based upon subsequent changes, the contract situation and customer needs. All equipment shall be operated and maintained at all times, in compliance with Borr Drilling standard operating manuals, policies and procedures, and within its stated operational limits or continuous rated capacity, in order to assure maximum operational efficiency.

